# AacerFlex TP

## Floor System Components

| Components Provided by Aacer Sports Flooring | Components Provided by Installer<br>AVAILABLE FROM AACER* |
|---|---|
| Subfloor Panels:<br>**16 SF per Panel**<br><br>Pre-assembled subfloor panels with resilient pads attached.<br><br> <br><br>NOTE: Quantities shown do not include waste. | Vapor Retarder*<br>**1 SF per SF**<br><br>1" Subfloor Staples*<br>**0.75 per SF**<br><br>2" Flooring Cleats or Staples*<br>**5.8 per SF**<br>- When installing 2-1/4" Flooring<br>- Fasteners applied 10" to 12" OC<br><br>OR<br><br>**8.7 per SF**<br>- If installing 1-1/2" Flooring<br>- Fasteners applied 10" to 12" OC<br><br>1/2" Solid Blocking<br><br>Duct Tape<br>for Vapor Retarder |