



PowerPlay Trax

Floor System Components



<p style="text-align: center;">Components Provided by Aacer Sports Flooring</p>	<p style="text-align: center;">Components Provided by Installer AVAILABLE FROM AACER*</p>
<p><u>Lower Subfloor Panels:</u> 17 SF per Panel</p> <p>Preassembled lower subfloor panels with resilient blanket cushion captured between top and bottom plywood layers.</p> <div style="border: 1px solid black; height: 60px; width: 100%;"></div> <p><u>Upper Subfloor Panels:</u> 17 SF per Panel</p> <div style="border: 1px solid black; height: 60px; width: 100%;"></div> <p><u>Anchor Assemblies</u> 0.177 Anchor Assemblies per SF</p> <div style="display: flex; align-items: center; margin-bottom: 10px;">  <div style="margin-left: 10px;">1-1/2" STEEL SPIKE ANCHOR</div> </div> <div style="display: flex; align-items: center;">  <div style="margin-left: 10px;">FENDER WASHER</div> </div> <p>NOTE: Quantities shown do not include waste.</p>	<p><u>Vapor Retarder</u>* 1 SF per SF</p> <p><u>3/4" Subfloor Staples</u>* 2.118 per SF</p> <p><u>1-3/4" Flooring Cleats or Staples</u>* 5.8 per SF</p> <ul style="list-style-type: none"> - When installing 2-1/4" Flooring - Fasteners applied 10" to 12" OC <p style="text-align: center;">OR</p> <p>8.7 per SF</p> <ul style="list-style-type: none"> - If installing 1-1/2" Flooring - Fasteners applied 10" to 12" OC <p><u>1-1/2" Solid Blocking</u></p> <p><u>Duct Tape</u> for Vapor Retarder</p> <p style="text-align: right;"><i>Note: Concrete anchors require 1/4" masonry bits</i></p>