

# Mechanical Operations



## Subfloor Installation

Aacer Sports Flooring and the Maple Flooring Manufacturers Association recommend only proceeding with the installation of hardwood athletic floor systems when permanent mechanicals are operating to provide environmental conditions that will exist when the facility is occupied. The anticipated temperature and humidity range should exist one week prior, during, and after installation.

The recommendation described above pertains to subfloor materials as well as the hardwood flooring installation to acceptably balance all wood components. Subfloors should not be installed prior to operation of permanent mechanical systems in an effort to accelerate the installation process.

END

REV A