AacerCush I Anchored

Floor System Components



Components	Components
Provided by	Provided by Installer
Aacer Sports Flooring	AVAILABLE FROM AACER *
Softwood Sleepers: 3 SF per Sleeper at 9" On Center	Vapor Retarder 1 SF per SF
2.67 SF per Sleeper if at 8" On Center	*
4' softwood sleepers with pre-drilled anchor pockets and resilient pads pre-attached.	 <u>2" Flooring Cleats or Staples</u> 7.1 per SF When installing 2-1/4" Flooring over Sleepers at 9" OC
	8.0 per SF - When installing 2-1/4" Flooring over Sleepers at 8" OC OR
Anchor Assemblies 0.67 per SF with sleepers at 9" OC	10.67 per SFIf installing 1-1/2" Flooring over Sleepers at 9" OC
0.75 per SF with sleepers at 8" OC	12.0 per SFIf installing 1-1/2" Flooring Over Sleepers at 8" OC
STEEL SPIKE ANCHOR SEALED WASHER RUBBER BUSHING	3/8" Solid Blocking
	<u>Duct Tape</u> for Vapor Retarder
NOTE: Quantities shown do not include waste.	