AacerCush I



Floor System Components

Components	Components
Provided by	Provided by Installer
Aacer Sports Flooring	AVAILABLE FROM AACER *
<u>Softwood Sleepers:</u> 3 SF per Sleeper at 9" On Center	<pre> Xapor Retarder * 1 SF per SF </pre>
2.67 SF per Sleeper if at 8" On Center	*
4' softwood sleepers with resilient pads pre-attached.	 <u>2" Flooring Cleats or Staples</u> 7.1 per SF When installing 2-1/4" Flooring over Sleepers at 9" OC
	 8.0 per SF When installing 2-1/4" Flooring over Sleepers at 8" OC
	OR
	10.67 per SF - If installing 1-1/2" Flooring over Sleepers at 9" OC
	12.0 per SF - If installing 1-1/2" Flooring Over Sleepers at 8" OC
	<u>3/8" Solid Blocking</u>
	<u>Duct Tape</u> for Vapor Retarder
NOTE: Quantities shown do not include waste.	