AacerFlex II CB





Components Components Provided by Provided by Installer Infinity Wood Floors AVAILABLE FROM INFINITY * Subfloor Panels: Vapor Retarder 16 SF per Panel 1 SF per SF Pre-assembled subfloor panels with resilient pads attached. 3/4" Subfloor Staples 0.75 per SF 1-1/2" Flooring Cleats or Staples 5.8 per SF - When installing 2-1/4" Flooring - Fasteners applied 10" to 12" OC OR 8.7 per SF - If installing 1-1/2" Flooring - Fasteners applied 10" to 12" OC 1" Solid Blocking **Duct Tape** for Vapor Retarder NOTE: Quantities shown do not include waste.