PowerPlay Edge



Floor System Components

Components Provided by Aacer Sports Flooring	Components Provided by Installer AVAILABLE FROM AACER *
Subfloor Panels: 16 SF per Panel Pre-assembled subfloor panels with resilient pads attached and pre-drilled anchor pockets provided.	Vapor Retarder 1 SF per SF <u>3/4" Subfloor Staples</u> 0.75 per SF <u>1-1/2" Flooring Cleats or Staples</u> 5.8 per SF - When installing 2-1/4" Flooring - Fasteners applied 10" to 12" OC OR 8.7 per SF - If installing 1-1/2" Flooring - Fasteners applied 10" to 12" OC <u>1/4" Solid Blocking</u> <u>Duct Tape</u>
NOTE: Quantities shown do not include waste.	for Vapor Retarder Note: Concrete anchors require 1/4" masonry bits