PowerSleeper



Floor System Components

Components	Components
Provided by	Provided by Installer
Aacer Sports Flooring	AVAILABLE FROM AACER *
Sleepers 10.67 SF per Sleeper 8' plywood sleepers with resilient pads preattached.	Vapor Retarder 1 SF per SF 15/32" Plywood Subfloor 32 SF per Sheet
STANDARD SLEEPER SPACING AT 16" ON CENTER	1" Subfloor Staples 1.125 per SF
	2" Flooring Cleats or Staples 5.8 per SF - When installing 2-1/4" Flooring - Fasteners applied 10" to 12" OC
	OR
	8.7 per SFIf installing 1-1/2" FlooringFasteners applied 10" to 12" OC
	1/2" Solid Blocking (for standard pads)
	<u>Duct Tape</u> for Vapor Retarder
NOTE: Quantities shown do not include waste.	