## Programme Dance I

### Floor System Components



# Components Provided by Infinity Wood Floors

# Components Provided by Installer

AVAILABLE FROM INFINITY \*

#### Lower Subfloor Panels:

17 SF per Panel

Preassembled lower subfloor panels with resilient blanket cushion captured between top and bottom plywood layers.




#### Upper SubfloorPanels:

17 SF per Panel



#### **Anchor Assemblies**

0.177 Anchor Assemblies per SF



NOTE: Quantities shown do not include waste.

Vapor Retarder 1 SF per SF

3/4" Subfloor Staples

2.118 per SF

1-1/2" Flooring Cleats or Staples

#### 5.8 per SF

- When installing 2-1/4" Flooring
- Fasteners applied 10" to 12" OC

OR

#### 8.7 per SF

- If installing 1-1/2" Flooring
- Fasteners applied 10" to 12" OC

1-1/2" Solid Blocking

<u>Duct Tape</u> for Vapor Retarder

Note: Concrete anchors require 1/4" masonry bits