## **ReClaim II**



## Floor System Components

Common on outo	<u>Canan an anta</u>
Components	Components
Provided by	Provided by Installer
Aacer Sports Flooring	AVAILABLE FROM AACER *
Subfloor Panels: 8 SF per Panel	Vapor Retarder 1 SF per SF
Pre-assembled subfloor panels with resilient pads attached and pre-drilled anchor pockets provided.	<u>3/4" Subfloor Staples</u> * 0.50 per SF
0	<ul> <li><u>1-1/2" Flooring Cleats or Staples</u></li> <li><b>5.8 per SF</b> <ul> <li>When installing 2-1/4" Flooring</li> <li>Fasteners applied 10" to 12" OC</li> </ul> </li> </ul>
~	OR
	<b>8.7 per SF</b> - If installing 1-1/2" Flooring - Fasteners applied 10" to 12" OC
Anchor Assemblies 0.375 Anchor Assemblies per SF	<u>1/8" Solid Blocking</u>
STEEL SPIKE ANCHOR	<u>Duct Tape</u> for Vapor Retarder
SEALED WASHER	
RUBBER SLEEVE	Note: Concrete anchors require 1/4" masonry bits
NOTE: Quantities shown do not include waste.	