## ScissorLoc IV





## Components Components Provided by Installer Provided by **Infinity Wood Floors** AVAILABLE FROM AACER \* Lower Subfloor Vapor Retarder 1.0436 LF Lineal Feet per SF 1 SF per SF 1 x 6 (3/4 x 5-1/2") 8' pine with resilient ECO pads pre-attached. 1-1/2" Subfloor Staples 5.2 per SF 6" SPACING OF LOWER SUBFLOOR 2" Flooring Cleats or Staples 5.8 per SF - When installing 2-1/4" Flooring - Fasteners applied 10" to 12" OC OR 8.7 per SF - If installing 1-1/2" Flooring - Fasteners applied 10" to 12" OC 2" SPACING OF UPPER SUBFLOOR 1/2" Solid Blocking Upper Subfloor 1.6 LF Lineal Feet per SF Duct Tape 1 x 6 (1/2" x 5-1/2") pine. for Vapor Retarder (Board lengths range from 6' to 16') NOTE: Quantities shown do not include waste.

REV A-23