





# PowerPlay Trax

## Floor System Components



Components Provided by Infinity Wood Floors	Components Provided by Installer AVAILABLE FROM INFINITY *
<p><u>Lower Subfloor Panels:</u> <b>17 SF per Panel</b></p> <p>Preassembled lower subfloor panels with resilient blanket cushion captured between top and bottom plywood layers.</p>  <p><u>Upper Subfloor Panels:</u> <b>17 SF per Panel</b></p>  <p><u>Anchor Assemblies</u> <b>0.177 Anchor Assemblies per SF</b></p> <div style="display: flex; align-items: center;">  <div style="margin-left: 10px;">STEEL SPIKE ANCHOR</div> </div> <div style="display: flex; align-items: center; margin-top: 10px;">  <div style="margin-left: 10px;">FENDER WASHER</div> </div> <p>NOTE: Quantities shown do not include waste.</p>	<p><u>Vapor Retarder</u> * <b>1 SF per SF</b></p> <p><u>3/4" Subfloor Staples</u> * <b>2.118 per SF</b></p> <p><u>1-1/2" Flooring Cleats or Staples</u> * <b>5.8 per SF</b></p> <ul style="list-style-type: none"> <li>- When installing 2-1/4" Flooring</li> <li>- Fasteners applied 10" to 12" OC</li> </ul> <p style="text-align: center;">OR</p> <p><b>8.7 per SF</b></p> <ul style="list-style-type: none"> <li>- If installing 1-1/2" Flooring</li> <li>- Fasteners applied 10" to 12" OC</li> </ul> <p><u>1-1/2" Solid Blocking</u></p> <p><u>Duct Tape</u> for Vapor Retarder</p> <p style="text-align: right;"><i>Note: Concrete anchors require 1/4" masonry bits</i></p>