






# Three Point

## Floor System Components



<p align="center"><b>Components Provided by Aacer Sports Floors</b></p>	<p align="center"><b>Components Provided by Installer</b> AVAILABLE FROM AACER *</p>
<p><u>Subfloor Panels:</u> <b>16 SF per Panel</b></p> <p>Preassembled subfloor panels with anchor pockets - resilient foam provided in rolls and installed separately</p>   <p align="center"><u>9/16" Foam Blanket</u> <b>1 SF per SF</b></p> <p><u>Anchor Assemblies</u> <b>0.188 Anchor Assemblies per SF</b></p>  <p>2-1/2" STEEL SPIKE ANCHOR</p>  <p>SEALED WASHER</p>  <p>1" RUBBER SLEEVE</p> <p>NOTE: Quantities shown do not include waste.</p>	<p><u>Vapor Retarder</u> * <b>1 SF per SF</b></p> <p><u>3/4" Subfloor Staples</u> * <b>0.813 per SF</b></p> <p><u>1-3/4" Flooring Cleats or Staples</u> * <b>5.8 per SF</b></p> <ul style="list-style-type: none"> <li>- When installing 2-1/4" Flooring</li> <li>- Fasteners applied 10" to 12" OC</li> </ul> <p align="center">OR</p> <p><b>8.7 per SF</b></p> <ul style="list-style-type: none"> <li>- If installing 1-1/2" Flooring</li> <li>- Fasteners applied 10" to 12" OC</li> </ul> <p><u>1/2" Solid Blocking</u></p> <p><u>Duct Tape</u> for Vapor Retarder</p> <p align="center"><i>Note: Concrete anchors require 1/4" masonry bits</i></p>