Programme Dance II (dual layer)

Floor System Components

AACER SPORTS FLOORING

Components Provided by Aacer Sports Flooring	Components Provided by Installer AVAILABLE FROM AACER *
Subfloor Panels: **16 SF per Panel** Pre-assembled subfloor panels with resilient pads attached. Additional layer installed separately. NOTE: Quantities shown do not include waste.	Vapor Retarder * **1 SF per SF** 3/4" Subfloor Staples * **0.75 per SF** 1-3/4" Flooring Cleats or Staples * **5.8 per SF** - When installing 2-1/4" Flooring - Fasteners applied 10" to 12" OC OR **8.7 per SF** - If installing 1-1/2" Flooring - Fasteners applied 10" to 12" OC 1" Solid Blocking Duct Tape for Vapor Retarder