MultiStage

Floor System Components

Components Provided by Aacer Sports Floors	Components Provided by Installer AVAILABLE FROM AACER *
Subfloor Panels: **16 SF per Panel** Pre-assembled subfloor panels with resilient pads attached. NOTE: Quantities shown do not include waste.	Vapor Retarder* **1 SF per SF** 1” Subfloor Staples* **0.75 per SF** 2” Flooring Cleats or Staples* **5.8 per SF** - When installing 2-1/4” Flooring - Fasteners applied 10” to 12” OC OR **8.7 per SF** - If installing 1-1/2” Flooring - Fasteners applied 10” to 12” OC 3/8” Solid Blocking Duct Tape for Vapor Retarder